

# McNally & Associates, INC.

UNDERGROUND/ABOVEGROUND STORAGE TANK TESTING SPECIALISTS  
CATHODIC PROTECTION SYSTEMS

97 LANSING DRIVE KENNESAW, GEORGIA 30144  
(770) 924-0705

"Serving Our Customers For Over 30 Years"

March 14, 2022

Gilmer County Schools  
Old Highway 5  
Ellijay, GA 30540


Install New 10,000 Gallon Aboveground Storage Tank,  
Associated Piping, Dispensers and Fuel Supply System

One (1) 10,000 Gallon Fireguard 2 Compartment  
(6000/4000) Aboveground Storage Tank With Tank Pad,  
Fuel Pump Supply System, Product Lines, New Suction  
Dispensers.

Price is all inclusive, includes freight and installation.

Total... ..\$97,810.00

Prices Subject To Change Without Notice

Harry McNally  
  
President



# Proposal

100 Perimeter Park Dr, STE H, Morrisville, NC 27560  
Phone: 919-838-7555

No. QUO-0218399

Revision: 2

Date: 3/14/2022

Sales Person : Dennis Dingler  
Phone No.: 770-548-5718  
E-Mail: ddingler@jfpetrogroup.com

Sold to: GILMER COUNTY SCHOOL SYSTEM  
43 LEGION RD  
Ellijay, GA 30540

Ship to: GILMER COUNTY SCHOOL SYSTEM  
43 LEGION RD  
Ellijay, GA 30540

Dispenser Net 10 Days \_\_\_\_\_ (Initial Here)

Terms:

Other Terms: Net 10 Days

PO:

Ship by:

## Comments

Sourcewell Information:

Gilmer County Shools - #14946

JF Petroleum Group - #092920-JFA

No.	Description	Qty.	Unit Price	Amount
<b>TANKS</b>				
TANK-STEEL-AST-DW	10,000 GALLON AST UL2085 SPLIT 6K/4K	1		

## Features

1 10000 Gallon Cylindrical Design FIREGUARD® TANK UL-2085

Application: Aboveground

Product stored: Gasoline

Type: DOUBLE WALL

Material: MILD CARBON STEEL

Diameter: 8'6" Length: 27'3"

1/4" Shell 5/16" Head 1/4" Outer Shell 5/16" Outer Head

Fittings: PER DRAWING

Exterior Coating: FIREGUARD WHITE

(2) 102" Diam x 6" High Saddles

STI Specification

Seal Welded to Tank

2 Emergency Vent - Flanged 8" - 16 Oz/Sq In

Includes:

Neoprene Gaskets, Nuts,

Bolts & Washers

1 Interstitial Monitor Pipe - 2"

1 Exterior Paint Touch Up Kit

Customer Initials \_\_\_\_\_ JF Petroleum Group Initials \_\_\_\_\_

1 Single Bulkhead for 96" Dia FIREGUARD®-SPLIT-(6K/4K)

#### TANK TOP EQUIPMENT

410140-002	QUICK SET PUMP RJ2, P75U1, 3/4HP	2
880-041-5	CONTROL BOX 115 V 1/3HP, 3/4HP, 1.5HP, 2HP MOTORS	2
515-2300 AC	SPILL CONT, AST REMOTE DUAL PORT, 3INX3IN, 15GAL	1
515-0300 AC	SPILL CONT, AST REMOTE FEMALE, 3IN, 15GAL, POST MT	1
305-0200 AA	ADAPTER, TIGHT FILL, TOP SEAL, 4IN, NO LUGS	2
305C-0100 AC	CAP, FILL TOP SEAL, 4IN	2
323-0100 AA	ADAPTER, VAPOR RECOVERY, 4INX3IN	1
323C-0100ACEVR	VAPOR RECOVERY CAP, 4IN	1
9095AA9300AEVR	OVERFILL PREVENTION VALVE, 3IN AST	2
354-0200 AV	VENT, UPDDRAFT, 2IN	1
723V-2203	VENT, PRESSURE VACUUM, 2IN WC, 8IN WC VAC	1
1228-03-5099	DROP TUBE 10FT	2

#### VALVES & FITTINGS

691-0700 1V	VALVE, BALL FULL PORT, 1.5IN, FORGED BRASS	2
910-1100 AV	VALVE, PRESSURE RELIEF, 1.5IN, 5-10FT	2
078DI-0200 AV	VALVE, PRESSURE RELIEF, .5IN, 40 PSI, DI	2
691-1000 1V	VALVE, BALL FULL PORT, 3IN, BRASS	2
246A-0400 AV	VALVE, SWING CHECK, 3IN, BRASS	2
610HH-0100 AR	HOSE RETRIEVER ASSEMBLY WITH 1IN HOSE HANGER	2

#### PIPING

FC20-SWM12	FLEX CONNECTOR, 2IN X 12IN, M SWIVEL, M	2
------------	---	---

#### MONITORING SYSTEMS

918-0400 AG	GAUGE, CLOCK ALARM 2IN, W/ DRP TB FLT, IN/FT	2
918GH0600012L	DIAL FACE, CUSTOM FACE PLATE 96X192 6000 GAL	2

#### ISLAND EQUIPMENT

434-14002 AK	AST DISPENSER PEDESTAL, 2 STABILIZER BARS, GASBOY	1
434CB-0150 1B	CONNECTION BOOT, 1.5 IN	2
434CB-0075 1B	CONNECTION BOOT, 3/4 IN	3
10P-0152	VALVE, SHEAR, 1.5IN, DBL POPPET, PRESSURE, CI	2
BOLLARD	6IN DIA. X 7FT LONG PIPE BOLLARD	20

#### DISPENSING EQUIPMENT

DISP-9853KXTW2 DF	REMOTE DISP, TWIN-2 PRODUCT SIDE LOAD	1
-------------------	---------------------------------------	---

#### FUEL MANAGEMENT SYSTEMS

CUSTOM COMMERCIAL EQ	2 Hose PV100 for Keypad Entry Only	1
----------------------	------------------------------------	---

#### HANGING HARDWARE

11BP-0400	NOZZLE, .75IN, UNLEADED, 11BP, 2 PIECE, BLACK, E10	2
-----------	--	---

Customer Initials \_\_\_\_\_ JF Petroleum Group Initials \_\_\_\_\_



8BL-0400	SPLASH GUARD, FILLGARD, .75IN, BLACK, 11A & 11B	2
241TPS-0241	SWIVEL, HOSE, .75IN, 2 PLANE	2
CTM75	MAGNETIC BREAKAWAY, 3/4IN	2
532-327-124-21269	HOSE, 3/4 X 12, WHIP FLEXSTEEL, HARDWALL	2
532-327-124-01269	HOSE, 3/4 IN X 12FT, MXM	2

#### ELECTRICAL EQUIPMENT

IA-ESOC	EMERGENCY STOP OPERATOR WITH LIFT-UP COVER	1
---------	--	---

#### MISCELLANEOUS EQUIPMENT

CUSTOM COMMERCIAL EQ	FUEL SYSTEM SIGNAGE	1
FREIGHT	FREIGHT	1
A411	20 LB ABC FIRE EXTINGUISHER	1
FT20PR	20LB FIRE EXT CABINET	1
CUSTOM COMMERCIAL EQ	ENGINEERED DRAWINGS	1

#### INSTALLATION

INSTALL LABOR	INSTALLATION	1
---------------	--------------	---

#### SERVICE TRAINING & STARTUP

SERVICE TECH	SERVICE STARTUP & TRAINING	1
--------------	----------------------------	---

EQUIPMENT:	109,387.12
SALES TAX:	7,657.10
FREIGHT:	312.50
INSTALLATION:	110,824.71
SERVICE:	2,190.00
TOTAL AMOUNT:	230,371.43

This proposal has applicable tax included.

#### SCOPE OF WORK

##### COMMERICAL SCOPE OF WORK

Provide the Customer with a detailed Construction schedule.

Hold an office Pre-Con meeting prior to ordering the equipment to verify quantities and sizes

Obtain State Department of Environmental Protection & Local Fire Marshall Permits for all work performed by JF Petroleum Group

Mobilize to the job site.

Work Sequence to be as follows:

##### ABOVEGROUND STORAGE TANK SCOPE OF WORK:

Pour Concrete under the Tank Saddles and Housekeeping Pad for Dispenser and FMS to the following spec: 4000 PSI Air Entrained

Provide Pipe Bollards as listed below at the aboveground tank(s)

XXX 6" Concrete Filled Painted OSHA Yellow

Customer Initials \_\_\_\_\_ JF Petroleum Group Initials \_\_\_\_\_